

## SCOPE OF WORK

The Bethany Y2022 Street Paving consists of hot mix patching, milling, taper milling, utility adjustments, leveling, and overlay as delineated in the following descriptions and quantities.

Construction of this contract shall conform to the Delaware Department of Transportation Standard Specifications dated June 2021, as amended by the Supplemental Specifications, the Special Provisions, the Standard Construction Details, and these Plans.

The proposed project includes, but is not necessarily limited to, the following locations, items and quantities:

### Base Bid:

1. **1<sup>st</sup> St.- S. Pennsylvania Ave. to 100' East (Intersection Only)**
  - a. 1<sup>st</sup> St. - Work consists of installing of pedestrian connections Type 1, 3" inch Type B. patching, 2" inch mill, 2" inch overlay, pavement striping and utility adjustments, #57 Stone for edge of road back up.
2. **4<sup>th</sup> St.- SR-1 to 100' East of S. Pennsylvania**
  - a. 4<sup>th</sup> St.- S. Pennsylvania to 100' East (Intersection Only)  
Work consists of install of pedestrian connections Type 1, 3" inch Type B. patching (if necessary), 2" inch mill, 2" Type C overlay, pavement striping and utility adjustments, #57 Stone for edge of road back up.
  - b. 4<sup>th</sup> St.- SR-1 to S. Pennsylvania Ave.-Work consists of milling 0" at CL and 2" at EOP, 3" Type B patching (if necessary), 2" Type C overlay, pavement striping, utility adjustments, #57 Stone for edge of road back up.
3. **Ashwood Ct.- Ashwood St. to Cul-de-Sac**
  - a. Ashwood Ct. - Work consists of milling 0" at CL and 2" at EOP, 3" Type B patching, 2" Type C overlay, line striping and utility adjustments, #57 Stone/ topsoil for edge of road back up.
4. **Beachwood Ln.- Kent Ave. to Cul-de-Sac**
  - a. Beachwood Ln. - Work consists of milling 2", 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.
5. **Central Blvd. Parking Lot- SR-1 to S. Pennsylvania Ave.**
  - a. Central Blvd. PL - Work consists of removing /resetting parking bumpers, taper milling tie in joint, 2" Type C overlay, pavement striping, #57 stone/ topsoil for edge of road back up.

**6. Central Blvd.- S. Pennsylvania to (East Intersection Only)**

- a. Central Blvd. (East Intersection Only)- Work consists of 2" patching, 2" Type C overlay, pavement striping.

**7. Delaware Ct.- Half Moon Ct. to Cul-de-Sac**

- a. Delaware Ct.- Work consists of taper milling 0" at CL and 2" at EOP, 3" Type B patching, 2" Type C overlay, line striping and utility adjustments, #57 Stone/ topsoil for edge of road back up.

**8. Sandstone Ct.- Half Moon Ct. to Cul-de-Sac**

- a. Sandstone Ct.- Work consists of taper milling 0" at CL and 2" at EOP, 3" Type B patching, 2" Type C overlay, line striping and utility adjustments, #57 Stone/ topsoil for edge of road back up.

**9. Old Post Ct.- Half Moon Ct. to Cul-de-Sac**

- a. Old Post Ct.- Work consists of taper milling 0" at CL and 2" at EOP, 3" Type B patching, 2" Type C overlay, line striping and utility adjustments, #57 Stone/ topsoil for edge of road back up.

**10. Rosewood Ct.- Half Moon Ct. to Cul-de-Sac**

- a. Rosewood Ct.- Work consists of taper milling 0" at CL and 2" at EOP, 3" Type B patching, 2" Type C overlay, line striping and utility adjustments, #57 Stone/ topsoil for edge of road back up.

**11. Eighth St.- Evans Ave. to End**

- a. Eighth St.- Work consists of milling of butt joints, 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.

**12. Seventh St.- Evans Ave. to End (West)**

- a. Seventh St.- Work consists of milling of butt joints, 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.

**13. Sixth St.- Evans Ave. to End (East)**

- a. Sixth St.- Work consists of milling of butt joints, 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.

**14. Fifth St.- Evans Ave. to Ends (East & West)**

- a. Fifth St.- Work consists of milling of butt joints, 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.

**15. Fourth St.- Evans Ave. to Ends (East & West)**

- a. Fourth St.- Work consists of milling of butt joints, 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.

**16. Third St.- Evans Ave.. to Ends (East & West)**

- a. Third St.- Work consists of milling of butt joints, 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.

**17. Second St.- Evans Ave. to End (West)**

- a. Second St.- Work consists of milling of butt joints, 3" Type B patching, 2" Type C overlay, pavement striping, utility adjustments, #57 Stone/ topsoil for edge of road back up.

**18. Tingle St.- SR26 to End**

- a. Tingle St.- Work consists of crack sealing.

**19. Hollywood St.- S. Pennsylvania Ave. to End**

- a. Hollywood St.- Work consist of 4" Type B & C patching, crack and joint sealing.

**20. Fairway Dr.- SR 26 to Collins St.**

- a. Fairway Dr.- Work consist of 4" Type B & C patching, crack and joint sealing.

**21. Salt Pond Rd.- Tree Top Ln. to Salt Pond Cr.**

- a. Salt Pond Rd.- Work consists of milling of butt joints, 3" Type B patching, Type C wedging, 2" Type C overlay, utility adjustments, pavement striping, #57 Stone/ topsoil for edge of road back up.

**22. Salt Pond Cr.- Salt Pond Rd. to Salt Pond Rd. (Loop)**

- a. Salt Pond Cr.- Work consists of milling of butt joints, 3" Type B patching, Type C wedging, 2" Type C overlay, utility adjustments, pavement striping, #57 Stone/ topsoil for edge of road back up.

**23. Second St.- S. Pennsylvania Ave. to (West Intersection Only)**

- a. Second St.- Work consists of 2" patching, 2" Type C overlay, pavement striping.

**24. Campbell Pl.- S. (Pennsylvania Ave. to East Intersection Only)**

- a. Campbell Pl.- Work consists of 2" patching, 2" Type C overlay, pavement striping.

**25. Parkwood St.- SR1 to S. Pennsylvania Ave.**

- a. Parkwood St.- Work consist of 4" Type B & C patching, crack and joint sealing.